

Engineered Construction Services

28 Pond Road PO Box 160 Raymond, Maine 04071 (207) 576-3745 326 Route 125 Brentwood, New Hampshire 03833 (603) 734-2301

Restore Capacity at Berth 6C

Owner: NAVFAC OICC, Portsmouth Naval Shipyard

Location: Kittery, Maine



Scope:

This project included repairs and improvements to Berth 6 at the Portsmouth Naval Shipyard (PNSY) to create two UFC compliant outfitting berths. Features of this project included the following:

- Installation of concrete curb along the offshore face of Berth 6
- Providing the required electrical, communication, and utility improvements (Steam, condensate, high pressure air, compressed air, fresh water, pure water, nitrogen, wheeler and sewer)
- Providing a raised concrete utility trench with precast covers
- Providing mooring hardware along the berth supported by new rock anchor foundations
- Providing concrete pads for Shipyard equipment







